



DISTRICT NIRMITHI KENDRA KANNUR

SUB COLLECTOR'S OFFICE COMPOUND, GUNDERT ROAD, THALASSERY PIN - 670101

PHONE 0490-2342729

FALSE CEILING WORK (II)

QUOTATION

No	Description of work	Rate in `	unit
I	ACCOSTIC FALSE CEILING		
	<p>Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with :</p>		m ²

A	Fully Perforated Gypsum Plaster Board of size 1200 x 2400x12.5 mm having approx. 15 % perforated area with perforation size and pattern as approved by the Engineer-in-charge and as per manufacturer's specification, with all 4 side tapered and backed by acoustical tissue with NRC value not less than 0.60		m ²
ADDITIONAL INCREASE IN RATES FOR HEIGHT ABOVE THREE FLOORS%			
SPECIAL CONDITIONS			
I	Rate will be valid for 6 months or till Nirmithi Kendra decides to invite new offers within 6 months		
II	Work should be executed as per the specifications mentioned in the schedule.		
III	rate should be quoted considering all wastages , scaffolding , ropes , lift etc		
IV	Weight of sections will be verified by Nirmithi Kendra at site at . under weight sections will be rejected without any compensation.		
V	Depending on progress of the work part payment can be released by Nirmithi kendra .		
VI	suppliers should agree to do works at any construction site of District nirmithi Kendra , kannur any where within kannur district.		
VIII	Sealed offer should reach at Nirmithi kendra kannur on or before 20-05-2026		
VIII	District Nirmithi Kendra reserve the right to accept or reject any offer without assigning any reason		
IX	Specify the brand name of sections to be used.....		
X	Rate will be applicable for three floors height. Mention percentage of increase in rates above 3 floors upto 5 floors in appropriate row.		
XI	Rate should be inclusive of all taxes and statutory payments.		
NAME ADDRESS AND PHONE NUMBER OF SUPPLIER			

Signature